

## Mariposa County Well and Septic Setback Requirements

	Domestic Well	Public Well	Flowing Stream (A)	Drainage Course/ Ephemeral Stream (B)	Cut or Fill Bank	Property Line	Lake, Pond, or Reservoir (D)	Center of Road	Structure Foundation	Leach Line	“D” Box
<b>Septic Tank or Sewer Line</b>	50 ft.	150 ft.	50 ft.	25 ft.	10 ft.	25 ft.	50 ft.	55 ft. or 25 ft., whichever is greater	5 ft.		5 ft.
<b>Leach Line</b>	100 ft.	150-200 ft.	100 ft.	50 ft.	4:1 (C)	25-50 ft.	200-400 ft.	55 ft. or 25 ft., Whichever is Greater	10 ft.	6 ft. (Center to Center)	5 ft.
<b>Seepage Pit</b>	150 ft.	150-200ft.	100	50	4:1 (C)	75 ft.	200-400 ft.	55 ft. or 25 ft., Whichever is Greater	10 ft.		
<b>Animal Enclosure</b>	100 ft.	100 ft.									
<b>Shared Water System</b>						5 ft.		Use 5 ft. P.L. Setback			

- (A) As measured from the line which defines the limit of a 10-year frequency flood.
- (B) As measured from the edge of the drainage course or stream.
- (C) Distance in feet equal four times the vertical height of the cut or fill.
- (D) As measured from the high water line.